
SULLIVAN COUNTY RURAL ELECTRIC CO-OP, INC.

P.O. BOX 65, ROUTE 87 FORKSVILLE, PENNSYLVANIA 18616

(800) 570 - 5081 email: screc@epix.net

(570) 924 - 3381 www.screc.com

INSTALLATION REQUIREMENTS OF POLE MOUNTED SERVICES FOR MOBILE HOMES AND SIMILAR APPLICATIONS



FURNISHED AND INSTALLED BY MEMBER

- ENTRANCE CABLE MUST BE INSTALLED ON POLE 100 AMP - # 2 ALUMINUM DR # 4 COPPER 200 AMP - 4/0 ALUMINUM DR 2/0 COPPER
- MEMBER DWNED 4 JAW UL APPROVED RINGLESS TYPE METERBASE WITH WEATHER TIGHT HUBS PURCHASED FROM AN ELECTRICAL SUPPLY COMPANY.

- FOUR (4) WIRE CABLE

- MEMBER DWNED SERVICE EQUIPMENT 100 AMP SERVICE WITH (6) 2-PDLE BREAKER SPACES, (12 PDLES) MINIMUM 200 AMP SERVICE WITH (6) 2-PDLE BREAKER SPACES, (12 PDLES) MINIMUM
- \bigcirc DNE (1) 5/8 \times 8 FT. COPPERWELD GROUND ROD.
- GROUND WIRE # 6 BARE COPPER FOR 100 AMP INSTALLATION AND # 4 BARE COPPER FOR A 200 AMP INSTALLATION.
 WHERE AVAILABLE, SERVICE SHOULD ALSO BE GROUNDED TO THE WELL CASING OR UNDERGROUND METALLIC WATER PIPING SYSTEM.
 GAS OR FUEL OIL PIPING SHALL NOT BE USED AS A GROUNDING ELECTRODE.
- (6) CABLE STRAPS TO BE PLACED 6 TO 10 IN. FROM VEATHERHEAD AND METERBASE AND AT THREE (3) FT. INTERVALS
- MEMBER SUPPLIED AND INSTALLED GRAY PVC SCHEDULE 40 CONDUIT, WITH 4 WIRE CABLE AT A MINIMUM DEPTH OF DNE FOOT PRIOR TO INSPECTION.

 100 AMP # 2 ALUMINUM OR # 4 COPPER 200 AMP 4/0 ALUMINUM OR 2/0 COPPER

PM-MH

07/18/07